



Notes:

1. Concrete Strength 32 MPa @ 28 days
2. Concrete contains MacMatrix 2" Fibers
3. Lid Sealed with Conseal CS-665
4. 2 - 20" Polylok Lids
5. Tank Weight: 7400 LBS
6. Lid Weight: 3180 LBS

DAN'S
Pre-Cast
LTD.

6100 Scott Rd.
Duncan, B.C.
250-746-7400
www.dansprecast.com

**1100 IMP. GAL. 2 COMP.
(5005 LITRES)**

Gals/inch 1st Chamber: 20.26 2nd Chamber: 9.47

DATE: OCTOBER 29, 2018

DRAWN BY:

EJG