



Notes:

1. Concrete Strength 32 MPa @ 28 days
2. Concrete contains MacMatrix 2" Fibers
3. Lid Sealed with Conseal CS-665
4. 2 - 20" Polylok Lids
5. Tank Weight: 4700 LBS
6. Lid Weight: 1600 LBS

DAN'S
Pre-Cast
LTD.

6100 Scott Rd.
Duncan, B.C.
250-746-7400
www.dansprecast.com

**600 IMP. GAL. 2 COMP.
(2722 LITRES)**

Gals/inch 1st Chamber: 12.33 2nd Chamber: 4.57

DATE: NOVEMBER 22, 2018

DRAWN BY:

EJG